



ref. PVS-120(100)-TL (Power-One_UK G59-3 Type Verification Test Report) Rev. 2018-02-08.docx

ENA Engineering Recommendation G59/3 Type Verification Test Report

Type Approval and manufacturer/supplier declaration of compliance with the requirements of Engineering Recommendation G59/3			
Type Test reference number	PVS-120-TL PVS-100-TL		
Generating unit technology	SOLAR GRID TIED INVERTER		
System Supplier name	Power-One Italy S.p.A.		
Address	Via S. Giorgio, 642 52028 Terranuova Bracciolini Arezzo - Italy		
Tel.	+39-055-91951	Fax	+39-055-9195248
E:mail	servicer.solarinverters@it.abb.com	Web site	www.abb.com/solarinverters www.abb.com
Maximum / Nominal rated capacity	Connection Option		
	PVS-120-TL: 120.0 kW (kW three phases) PVS-100-TL: 100.0 kW (kW three phases)		
We, Power-One Italy S.p.A., as manufacturer/supplier of Generating Unit, certifies that all products manufactured/supplied by the company with the above Type Test reference number will be manufactured and tested to ensure that they perform as stated in this document, prior to shipment to site and that no site modifications are required to ensure that the products meet all the requirements of G59/3.			
Attachment: Extract of Test Report Ref. 28111159 011 , released by TÜV Rheinland.			

Terranuova B.ni, 2017 February 08

Claudio Redolfi
(Quality & OPEX Manager)

Cristiano Ensoli
(Manager Quality)

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 1 von 19
 Page 1 of 19

Type of System:	Solar Grid tied inverter							
System Manufacturer: Manufacturer data:	Power-One Italy S.p.A. Via S. Giorgio 642, 52028 Terranuova Bracciolini (AR) - Italy							
Reference test report:	28111159 011 Issued by TÜV Rheinland Italia S.r.l.							
Measuring period:	From 01/09/2017 to 15/11/2017							
Type Test reference number: Pacr / Pacmax <i>(Rated AC Power / Maximum AC output Power)</i>	<table border="1"> <thead> <tr> <th>Models</th> <th>Pacr / Pacmax</th> </tr> </thead> <tbody> <tr> <td>PVS-100-TL</td> <td>100 kW / 100kW</td> </tr> <tr> <td>PVS-120-TL</td> <td>120 kW / 120 kW</td> </tr> </tbody> </table>		Models	Pacr / Pacmax	PVS-100-TL	100 kW / 100kW	PVS-120-TL	120 kW / 120 kW
Models	Pacr / Pacmax							
PVS-100-TL	100 kW / 100kW							
PVS-120-TL	120 kW / 120 kW							
Software version:	Bundle Firmware Update Version*: not less than: 1749E for PVS-120-TL 1749F for PVS-100-TL standard selection: UK G59							
Rated Voltage:	400/480 V, 3W+N+PE & 3W+PE PVS-100(120)-TL							
Note *:	<p>“Update version” identifies the Bundle Firmware Features by a sequential code: xxxxy where:</p> <ul style="list-style-type: none"> • xxxx is a number indicates Year (two digits) and Week (two digits) • y is a letter from A to G indicates Day (from Sunday = A to Saturday=G) 							

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 2 von 19
 Page 2 of 19

Power Quality. Harmonics.
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

- Test performed on the model PVS-100-TL:

Order	100%						Limits Rsce33	Result
	Phase R [A]	Phase S [A]	Phase T [A]	Phase R [%]	Phase S [%]	Phase T [%]		
0								
1	143.742	143.391	143.890					
2	0.209	0.317	0.514	0.15%	0.22%	0.36%		
3	0.115	0.155	0.216	0.08%	0.11%	0.15%		
4	0.263	0.246	0.256	0.18%	0.17%	0.18%		
5	0.646	0.621	0.603	0.45%	0.43%	0.42%	10.700	PASS
6	0.105	0.108	0.097	0.07%	0.08%	0.07%		
7	0.629	0.586	0.692	0.44%	0.41%	0.48%	7.200	PASS
8	0.149	0.154	0.142	0.10%	0.11%	0.10%		
9	0.198	0.205	0.206	0.14%	0.14%	0.14%		
10	0.201	0.251	0.261	0.14%	0.17%	0.18%		
11	1.443	1.327	1.302	1.00%	0.93%	0.90%	3.100	PASS
12	0.152	0.162	0.101	0.11%	0.11%	0.07%		
13	0.444	0.440	0.470	0.31%	0.31%	0.33%	2.000	PASS
14	0.078	0.074	0.082	0.05%	0.05%	0.06%		
15	0.057	0.055	0.052	0.04%	0.04%	0.04%		
16	0.062	0.059	0.047	0.04%	0.04%	0.03%		
17	0.119	0.118	0.114	0.08%	0.08%	0.08%		
18	0.026	0.027	0.026	0.02%	0.02%	0.02%		
19	0.094	0.097	0.096	0.07%	0.07%	0.07%		
20	0.021	0.015	0.019	0.01%	0.01%	0.01%		
21	0.016	0.011	0.014	0.01%	0.01%	0.01%		
22	0.016	0.014	0.016	0.01%	0.01%	0.01%		
23	0.050	0.052	0.051	0.03%	0.04%	0.04%		
24	0.009	0.007	0.006	0.01%	0.01%	0.00%		
25	0.049	0.047	0.051	0.03%	0.03%	0.04%		
26	0.022	0.019	0.023	0.02%	0.01%	0.02%		
27	0.028	0.022	0.029	0.02%	0.02%	0.02%		
28	0.046	0.036	0.048	0.03%	0.03%	0.03%		
29	0.056	0.056	0.064	0.04%	0.04%	0.04%		
30	0.054	0.045	0.064	0.04%	0.03%	0.04%		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 3 von 19
 Page 3 of 19

31	0.079	0.067	0.082	0.05%	0.05%	0.06%		
32	0.089	0.084	0.100	0.06%	0.06%	0.07%		
33	0.122	0.100	0.120	0.08%	0.07%	0.08%		
THD	1.29%	1.23%	1.28%					

60%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	86.317	86.109	86.289					
2	0.168	0.276	0.397	0.19%	0.32%	0.46%		
3	0.146	0.144	0.093	0.17%	0.17%	0.11%		
4	0.268	0.257	0.242	0.31%	0.30%	0.28%		
5	0.568	0.607	0.598	0.66%	0.71%	0.69%	10.700	PASS
6	0.107	0.109	0.106	0.12%	0.13%	0.12%		
7	0.590	0.559	0.607	0.68%	0.65%	0.70%	7.200	PASS
8	0.146	0.158	0.161	0.17%	0.18%	0.19%		
9	0.156	0.159	0.145	0.18%	0.18%	0.17%		
10	0.214	0.264	0.260	0.25%	0.31%	0.30%		
11	1.577	1.459	1.479	1.83%	1.69%	1.71%	3.100	PASS
12	0.175	0.148	0.098	0.20%	0.17%	0.11%		
13	0.424	0.424	0.425	0.49%	0.49%	0.49%	2.000	PASS
14	0.072	0.074	0.075	0.08%	0.09%	0.09%		
15	0.047	0.042	0.042	0.05%	0.05%	0.05%		
16	0.044	0.038	0.034	0.05%	0.04%	0.04%		
17	0.117	0.118	0.117	0.14%	0.14%	0.14%		
18	0.017	0.015	0.014	0.02%	0.02%	0.02%		
19	0.103	0.106	0.107	0.12%	0.12%	0.12%		
20	0.009	0.008	0.006	0.01%	0.01%	0.01%		
21	0.006	0.004	0.004	0.01%	0.00%	0.00%		
22	0.006	0.004	0.004	0.01%	0.00%	0.00%		
23	0.068	0.074	0.074	0.08%	0.09%	0.09%		
24	0.001	0.002	0.002	0.00%	0.00%	0.00%		
25	0.060	0.057	0.057	0.07%	0.07%	0.07%		
26	0.004	0.003	0.004	0.00%	0.00%	0.00%		
27	0.008	0.003	0.003	0.01%	0.00%	0.00%		
28	0.023	0.012	0.010	0.03%	0.01%	0.01%		
29	0.051	0.041	0.051	0.06%	0.05%	0.06%		
30	0.067	0.053	0.069	0.08%	0.06%	0.08%		
31	0.111	0.096	0.056	0.13%	0.11%	0.07%		
32	0.192	0.128	0.190	0.22%	0.15%	0.22%		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 4 von 19
 Page 4 of 19

33	0.238	0.129	0.189	0.28%	0.15%	0.22%		
THD	2.24%	2.14%	2.19%					

33%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	43.401	43.292	43.391					
2	0.184	0.246	0.351	0.42%	0.57%	0.81%		
3	0.131	0.121	0.080	0.30%	0.28%	0.18%		
4	0.228	0.235	0.216	0.52%	0.54%	0.50%		
5	0.254	0.274	0.248	0.59%	0.63%	0.57%	10.700	PASS
6	0.090	0.096	0.089	0.21%	0.22%	0.21%		
7	0.269	0.255	0.289	0.62%	0.59%	0.67%	7.200	PASS
8	0.123	0.136	0.138	0.28%	0.31%	0.32%		
9	0.125	0.124	0.125	0.29%	0.29%	0.29%		
10	0.199	0.198	0.196	0.46%	0.46%	0.45%		
11	1.058	0.945	0.999	2.44%	2.18%	2.30%	3.100	PASS
12	0.122	0.123	0.082	0.28%	0.28%	0.19%		
13	0.600	0.592	0.605	1.38%	1.37%	1.39%	2.000	PASS
14	0.081	0.080	0.082	0.19%	0.18%	0.19%		
15	0.049	0.038	0.042	0.11%	0.09%	0.10%		
16	0.041	0.037	0.039	0.09%	0.09%	0.09%		
17	0.115	0.116	0.113	0.27%	0.27%	0.26%		
18	0.008	0.011	0.007	0.02%	0.03%	0.02%		
19	0.070	0.064	0.067	0.16%	0.15%	0.16%		
20	0.004	0.004	0.002	0.01%	0.01%	0.01%		
21	0.001	0.000	0.000	0.00%	0.00%	0.00%		
22	0.000	0.000	0.001	0.00%	0.00%	0.00%		
23	0.000	0.000	0.000	0.00%	0.00%	0.00%		
24	0.000	0.000	0.000	0.00%	0.00%	0.00%		
25	0.003	0.000	0.002	0.01%	0.00%	0.00%		
26	0.003	0.002	0.002	0.01%	0.01%	0.00%		
27	0.004	0.001	0.003	0.01%	0.00%	0.01%		
28	0.007	0.005	0.009	0.02%	0.01%	0.02%		
29	0.099	0.044	0.067	0.23%	0.10%	0.15%		
30	0.134	0.166	0.143	0.31%	0.38%	0.33%		
31	0.085	0.076	0.114	0.20%	0.17%	0.26%		
32	0.060	0.031	0.001	0.14%	0.07%	0.00%		
33	0.002	0.000	0.003	0.00%	0.00%	0.01%		

THD 3.16% 2.99% 3.12%

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 5 von 19
 Page 5 of 19

- Test performed on the model PVS-120-TL:

100%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	143.742	143.391	143.890					
2	0.209	0.317	0.514	0.15%	0.22%	0.36%		
3	0.115	0.155	0.216	0.08%	0.11%	0.15%		
4	0.263	0.246	0.256	0.18%	0.17%	0.18%		
5	0.646	0.621	0.603	0.45%	0.43%	0.42%	10.700	PASS
6	0.105	0.108	0.097	0.07%	0.08%	0.07%		
7	0.629	0.586	0.692	0.44%	0.41%	0.48%	7.200	PASS
8	0.149	0.154	0.142	0.10%	0.11%	0.10%		
9	0.198	0.205	0.206	0.14%	0.14%	0.14%		
10	0.201	0.251	0.261	0.14%	0.17%	0.18%		
11	1.443	1.327	1.302	1.00%	0.93%	0.90%	3.100	PASS
12	0.152	0.162	0.101	0.11%	0.11%	0.07%		
13	0.444	0.440	0.470	0.31%	0.31%	0.33%	2.000	PASS
14	0.078	0.074	0.082	0.05%	0.05%	0.06%		
15	0.057	0.055	0.052	0.04%	0.04%	0.04%		
16	0.062	0.059	0.047	0.04%	0.04%	0.03%		
17	0.119	0.118	0.114	0.08%	0.08%	0.08%		
18	0.026	0.027	0.026	0.02%	0.02%	0.02%		
19	0.094	0.097	0.096	0.07%	0.07%	0.07%		
20	0.021	0.015	0.019	0.01%	0.01%	0.01%		
21	0.016	0.011	0.014	0.01%	0.01%	0.01%		
22	0.016	0.014	0.016	0.01%	0.01%	0.01%		
23	0.050	0.052	0.051	0.03%	0.04%	0.04%		
24	0.009	0.007	0.006	0.01%	0.01%	0.00%		
25	0.049	0.047	0.051	0.03%	0.03%	0.04%		
26	0.022	0.019	0.023	0.02%	0.01%	0.02%		
27	0.028	0.022	0.029	0.02%	0.02%	0.02%		
28	0.046	0.036	0.048	0.03%	0.03%	0.03%		
29	0.056	0.056	0.064	0.04%	0.04%	0.04%		
30	0.054	0.045	0.064	0.04%	0.03%	0.04%		
31	0.079	0.067	0.082	0.05%	0.05%	0.06%		
32	0.089	0.084	0.100	0.06%	0.06%	0.07%		
33	0.122	0.100	0.120	0.08%	0.07%	0.08%		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 6 von 19
 Page 6 of 19

THD 1.29% 1.23% 1.28%

60%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	86.317	86.109	86.289					
2	0.168	0.276	0.397	0.19%	0.32%	0.46%		
3	0.146	0.144	0.093	0.17%	0.17%	0.11%		
4	0.268	0.257	0.242	0.31%	0.30%	0.28%		
5	0.568	0.607	0.598	0.66%	0.71%	0.69%	10.700	PASS
6	0.107	0.109	0.106	0.12%	0.13%	0.12%		
7	0.590	0.559	0.607	0.68%	0.65%	0.70%	7.200	PASS
8	0.146	0.158	0.161	0.17%	0.18%	0.19%		
9	0.156	0.159	0.145	0.18%	0.18%	0.17%		
10	0.214	0.264	0.260	0.25%	0.31%	0.30%		
11	1.577	1.459	1.479	1.83%	1.69%	1.71%	3.100	PASS
12	0.175	0.148	0.098	0.20%	0.17%	0.11%		
13	0.424	0.424	0.425	0.49%	0.49%	0.49%	2.000	PASS
14	0.072	0.074	0.075	0.08%	0.09%	0.09%		
15	0.047	0.042	0.042	0.05%	0.05%	0.05%		
16	0.044	0.038	0.034	0.05%	0.04%	0.04%		
17	0.117	0.118	0.117	0.14%	0.14%	0.14%		
18	0.017	0.015	0.014	0.02%	0.02%	0.02%		
19	0.103	0.106	0.107	0.12%	0.12%	0.12%		
20	0.009	0.008	0.006	0.01%	0.01%	0.01%		
21	0.006	0.004	0.004	0.01%	0.00%	0.00%		
22	0.006	0.004	0.004	0.01%	0.00%	0.00%		
23	0.068	0.074	0.074	0.08%	0.09%	0.09%		
24	0.001	0.002	0.002	0.00%	0.00%	0.00%		
25	0.060	0.057	0.057	0.07%	0.07%	0.07%		
26	0.004	0.003	0.004	0.00%	0.00%	0.00%		
27	0.008	0.003	0.003	0.01%	0.00%	0.00%		
28	0.023	0.012	0.010	0.03%	0.01%	0.01%		
29	0.051	0.041	0.051	0.06%	0.05%	0.06%		
30	0.067	0.053	0.069	0.08%	0.06%	0.08%		
31	0.111	0.096	0.056	0.13%	0.11%	0.07%		
32	0.192	0.128	0.190	0.22%	0.15%	0.22%		
33	0.238	0.129	0.189	0.28%	0.15%	0.22%		

THD 2.24% 2.14% 2.19%

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 7 von 19
 Page 7 of 19

33%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	43.401	43.292	43.391					
2	0.184	0.246	0.351	0.42%	0.57%	0.81%		
3	0.131	0.121	0.080	0.30%	0.28%	0.18%		
4	0.228	0.235	0.216	0.52%	0.54%	0.50%		
5	0.254	0.274	0.248	0.59%	0.63%	0.57%	10.700	PASS
6	0.090	0.096	0.089	0.21%	0.22%	0.21%		
7	0.269	0.255	0.289	0.62%	0.59%	0.67%	7.200	PASS
8	0.123	0.136	0.138	0.28%	0.31%	0.32%		
9	0.125	0.124	0.125	0.29%	0.29%	0.29%		
10	0.199	0.198	0.196	0.46%	0.46%	0.45%		
11	1.058	0.945	0.999	2.44%	2.18%	2.30%	3.100	PASS
12	0.122	0.123	0.082	0.28%	0.28%	0.19%		
13	0.600	0.592	0.605	1.38%	1.37%	1.39%	2.000	PASS
14	0.081	0.080	0.082	0.19%	0.18%	0.19%		
15	0.049	0.038	0.042	0.11%	0.09%	0.10%		
16	0.041	0.037	0.039	0.09%	0.09%	0.09%		
17	0.115	0.116	0.113	0.27%	0.27%	0.26%		
18	0.008	0.011	0.007	0.02%	0.03%	0.02%		
19	0.070	0.064	0.067	0.16%	0.15%	0.16%		
20	0.004	0.004	0.002	0.01%	0.01%	0.01%		
21	0.001	0.000	0.000	0.00%	0.00%	0.00%		
22	0.000	0.000	0.001	0.00%	0.00%	0.00%		
23	0.000	0.000	0.000	0.00%	0.00%	0.00%		
24	0.000	0.000	0.000	0.00%	0.00%	0.00%		
25	0.003	0.000	0.002	0.01%	0.00%	0.00%		
26	0.003	0.002	0.002	0.01%	0.01%	0.00%		
27	0.004	0.001	0.003	0.01%	0.00%	0.01%		
28	0.007	0.005	0.009	0.02%	0.01%	0.02%		
29	0.099	0.044	0.067	0.23%	0.10%	0.15%		
30	0.134	0.166	0.143	0.31%	0.38%	0.33%		
31	0.085	0.076	0.114	0.20%	0.17%	0.26%		
32	0.060	0.031	0.001	0.14%	0.07%	0.00%		
33	0.002	0.000	0.003	0.00%	0.00%	0.01%		
THD	3.16%	2.99%	3.12%					

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 8 von 19
 Page 8 of 19

PVS 120-TL Power=100%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	143.742	143.391	143.890					
2	0.209	0.317	0.514	0.15%	0.22%	0.36%		
3	0.115	0.155	0.216	0.08%	0.11%	0.15%		
4	0.263	0.246	0.256	0.18%	0.17%	0.18%		
5	0.646	0.621	0.603	0.45%	0.43%	0.42%	10.700	PASS
6	0.105	0.108	0.097	0.07%	0.08%	0.07%		
7	0.629	0.586	0.692	0.44%	0.41%	0.48%	7.200	PASS
8	0.149	0.154	0.142	0.10%	0.11%	0.10%		
9	0.198	0.205	0.206	0.14%	0.14%	0.14%		
10	0.201	0.251	0.261	0.14%	0.17%	0.18%		
11	1.443	1.327	1.302	1.00%	0.93%	0.90%	3.100	PASS
12	0.152	0.162	0.101	0.11%	0.11%	0.07%		
13	0.444	0.440	0.470	0.31%	0.31%	0.33%	2.000	PASS
14	0.078	0.074	0.082	0.05%	0.05%	0.06%		
15	0.057	0.055	0.052	0.04%	0.04%	0.04%		
16	0.062	0.059	0.047	0.04%	0.04%	0.03%		
17	0.119	0.118	0.114	0.08%	0.08%	0.08%		
18	0.026	0.027	0.026	0.02%	0.02%	0.02%		
19	0.094	0.097	0.096	0.07%	0.07%	0.07%		
20	0.021	0.015	0.019	0.01%	0.01%	0.01%		
21	0.016	0.011	0.014	0.01%	0.01%	0.01%		
22	0.016	0.014	0.016	0.01%	0.01%	0.01%		
23	0.050	0.052	0.051	0.03%	0.04%	0.04%		
24	0.009	0.007	0.006	0.01%	0.01%	0.00%		
25	0.049	0.047	0.051	0.03%	0.03%	0.04%		
26	0.022	0.019	0.023	0.02%	0.01%	0.02%		
27	0.028	0.022	0.029	0.02%	0.02%	0.02%		
28	0.046	0.036	0.048	0.03%	0.03%	0.03%		
29	0.056	0.056	0.064	0.04%	0.04%	0.04%		
30	0.054	0.045	0.064	0.04%	0.03%	0.04%		
31	0.079	0.067	0.082	0.05%	0.05%	0.06%		
32	0.089	0.084	0.100	0.06%	0.06%	0.07%		
33	0.122	0.100	0.120	0.08%	0.07%	0.08%		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 9 von 19
 Page 9 of 19

PVS 120-TL Power=60%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	86.317	86.109	86.289					
2	0.168	0.276	0.397	0.12%	0.19%	0.28%		
3	0.146	0.144	0.093	0.10%	0.10%	0.06%		
4	0.268	0.257	0.242	0.19%	0.18%	0.17%		
5	0.568	0.607	0.598	0.40%	0.42%	0.42%	10.700	PASS
6	0.107	0.109	0.106	0.07%	0.08%	0.07%		
7	0.590	0.559	0.607	0.41%	0.39%	0.42%	7.200	PASS
8	0.146	0.158	0.161	0.10%	0.11%	0.11%		
9	0.156	0.159	0.145	0.11%	0.11%	0.10%		
10	0.214	0.264	0.260	0.15%	0.18%	0.18%		
11	1.577	1.459	1.479	1.10%	1.02%	1.03%	3.100	PASS
12	0.175	0.148	0.098	0.12%	0.10%	0.07%		
13	0.424	0.424	0.425	0.29%	0.30%	0.30%	2.000	PASS
14	0.072	0.074	0.075	0.05%	0.05%	0.05%		
15	0.047	0.042	0.042	0.03%	0.03%	0.03%		
16	0.044	0.038	0.034	0.03%	0.03%	0.02%		
17	0.117	0.118	0.117	0.08%	0.08%	0.08%		
18	0.017	0.015	0.014	0.01%	0.01%	0.01%		
19	0.103	0.106	0.107	0.07%	0.07%	0.07%		
20	0.009	0.008	0.006	0.01%	0.01%	0.00%		
21	0.006	0.004	0.004	0.00%	0.00%	0.00%		
22	0.006	0.004	0.004	0.00%	0.00%	0.00%		
23	0.068	0.074	0.074	0.05%	0.05%	0.05%		
24	0.001	0.002	0.002	0.00%	0.00%	0.00%		
25	0.060	0.057	0.057	0.04%	0.04%	0.04%		
26	0.004	0.003	0.004	0.00%	0.00%	0.00%		
27	0.008	0.003	0.003	0.01%	0.00%	0.00%		
28	0.023	0.012	0.010	0.02%	0.01%	0.01%		
29	0.051	0.041	0.051	0.04%	0.03%	0.04%		
30	0.067	0.053	0.069	0.05%	0.04%	0.05%		
31	0.111	0.096	0.056	0.08%	0.07%	0.04%		
32	0.192	0.128	0.190	0.13%	0.09%	0.13%		
33	0.238	0.129	0.189	0.17%	0.09%	0.13%		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 10 von 19
 Page 10 of 19

PVS 120-TL Power=33%								
Order	Phase R	Phase S	Phase T	Phase R	Phase S	Phase T	Limits	Result
	[A]	[A]	[A]	[%]	[%]	[%]	Rsce33	
0								
1	43.401	43.292	43.391					
2	0.184	0.246	0.351	0.13%	0.17%	0.24%		
3	0.131	0.121	0.080	0.09%	0.08%	0.06%		
4	0.228	0.235	0.216	0.16%	0.16%	0.15%		
5	0.254	0.274	0.248	0.18%	0.19%	0.17%	10.700	PASS
6	0.090	0.096	0.089	0.06%	0.07%	0.06%		
7	0.269	0.255	0.289	0.19%	0.18%	0.20%	7.200	PASS
8	0.123	0.136	0.138	0.09%	0.09%	0.10%		
9	0.125	0.124	0.125	0.09%	0.09%	0.09%		
10	0.199	0.198	0.196	0.14%	0.14%	0.14%		
11	1.058	0.945	0.999	0.74%	0.66%	0.69%	3.100	PASS
12	0.122	0.123	0.082	0.08%	0.09%	0.06%		
13	0.600	0.592	0.605	0.42%	0.41%	0.42%	2.000	PASS
14	0.081	0.080	0.082	0.06%	0.06%	0.06%		
15	0.049	0.038	0.042	0.03%	0.03%	0.03%		
16	0.041	0.037	0.039	0.03%	0.03%	0.03%		
17	0.115	0.116	0.113	0.08%	0.08%	0.08%		
18	0.008	0.011	0.007	0.01%	0.01%	0.00%		
19	0.070	0.064	0.067	0.05%	0.04%	0.05%		
20	0.004	0.004	0.002	0.00%	0.00%	0.00%		
21	0.001	0.000	0.000	0.00%	0.00%	0.00%		
22	0.000	0.000	0.001	0.00%	0.00%	0.00%		
23	0.000	0.000	0.000	0.00%	0.00%	0.00%		
24	0.000	0.000	0.000	0.00%	0.00%	0.00%		
25	0.003	0.000	0.002	0.00%	0.00%	0.00%		
26	0.003	0.002	0.002	0.00%	0.00%	0.00%		
27	0.004	0.001	0.003	0.00%	0.00%	0.00%		
28	0.007	0.005	0.009	0.00%	0.00%	0.01%		
29	0.099	0.044	0.067	0.07%	0.03%	0.05%		
30	0.134	0.166	0.143	0.09%	0.12%	0.10%		
31	0.085	0.076	0.114	0.06%	0.05%	0.08%		
32	0.060	0.031	0.001	0.04%	0.02%	0.00%		
33	0.002	0.000	0.003	0.00%	0.00%	0.00%		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 11 von 19
 Page 11 of 19

Power Quality. Voltage fluctuations and Flicker.						
Phase 1 33%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	dmax
1	0.199	0.895	0.716		0.10%	1.02%
2	0.195	0.877	0.674		0.10%	1.02%
3	0.198	0.890	0.706		0.10%	1.02%
4	0.197	0.887	0.698		0.10%	1.02%
5	0.196	0.882	0.685		0.10%	1.02%
6	0.195	0.876	0.673		0.10%	1.02%
7	0.199	0.895	0.716		0.10%	1.02%
8	0.195	0.877	0.674		0.10%	1.02%
9	0.198	0.890	0.706		0.10%	1.02%
10	0.197	0.887	0.698		0.10%	1.02%
11	0.196	0.882	0.685		0.10%	1.02%
12	0.195	0.876	0.673		0.10%	1.02%
			7.588	0.858		
Phase 2 33%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	dmax
1	0.204	0.917	0.772		0.10%	1.02%
2	0.203	0.912	0.759		0.10%	1.02%
3	0.204	0.918	0.775		0.10%	1.02%
4	0.211	0.949	0.854		0.10%	1.02%
5	0.207	0.929	0.802		0.10%	1.02%
6	0.204	0.917	0.770		0.10%	1.02%
7	0.204	0.917	0.772		0.10%	1.02%
8	0.203	0.912	0.759		0.10%	1.02%
9	0.204	0.918	0.775		0.10%	1.02%
10	0.211	0.949	0.854		0.10%	1.02%
11	0.207	0.929	0.802		0.10%	1.02%
12	0.204	0.917	0.770		0.10%	1.02%
			9.461	0.924		
Phase 3 33%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	Dmax
1	0.208	0.935	0.818		0.10%	1.02%
2	0.207	0.932	0.810		0.10%	1.02%
3	0.209	0.938	0.826		0.10%	1.02%
4	0.188	0.847	0.608		0.10%	1.02%
5	0.210	0.944	0.841		0.10%	1.02%
6	0.208	0.934	0.814		0.10%	1.02%
7	0.208	0.935	0.818		0.10%	1.02%
8	0.207	0.932	0.810		0.10%	1.02%
9	0.209	0.938	0.826		0.10%	1.02%
10	0.188	0.847	0.608		0.10%	1.02%
11	0.210	0.944	0.841		0.10%	1.02%
12	0.208	0.934	0.814		0.10%	1.02%
			9.431	0.923		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 12 von 19
 Page 12 of 19

Phase 1 60%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	dmax
1	0.209	0.941	0.832		0.10%	1.02%
2	0.211	0.947	0.850		0.10%	1.02%
3	0.209	0.941	0.834		0.10%	1.02%
4	0.205	0.922	0.783		0.10%	1.02%
5	0.207	0.933	0.811		0.10%	1.02%
6	0.206	0.926	0.795		0.10%	1.02%
7	0.209	0.941	0.832		0.10%	1.02%
8	0.211	0.947	0.850		0.10%	1.02%
9	0.209	0.941	0.834		0.10%	1.02%
10	0.205	0.922	0.783		0.10%	1.02%
11	0.207	0.933	0.811		0.10%	1.02%
12	0.206	0.926	0.795		0.10%	1.02%
			8.977	0.908		
Phase 2 60%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	dmax
1	0.202	0.908	0.749		0.10%	1.02%
2	0.217	0.976	0.930		0.10%	1.02%
3	0.220	0.988	0.965		0.10%	1.02%
4	0.219	0.983	0.950		0.10%	1.02%
5	0.218	0.979	0.939		0.10%	1.02%
6	0.214	0.962	0.889		0.10%	1.02%
7	0.220	0.989	0.968		0.10%	1.02%
8	0.217	0.976	0.930		0.10%	1.02%
9	0.220	0.988	0.965		0.10%	1.02%
10	0.219	0.983	0.950		0.10%	1.02%
11	0.218	0.979	0.939		0.10%	1.02%
12	0.214	0.962	0.889		0.10%	1.02%
			11.063	0.973		
Phase 3 60%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	Dmax
1	0.196	0.882	0.687		0.10%	1.02%
2	0.196	0.880	0.682		0.10%	1.02%
3	0.197	0.887	0.698		0.10%	1.02%
4	0.193	0.869	0.656		0.10%	1.02%
5	0.196	0.880	0.681		0.10%	1.02%
6	0.193	0.866	0.650		0.10%	1.02%
7	0.196	0.882	0.687		0.10%	1.02%
8	0.196	0.880	0.682		0.10%	1.02%
9	0.197	0.887	0.698		0.10%	1.02%
10	0.193	0.869	0.656		0.10%	1.02%
11	0.196	0.880	0.681		0.10%	1.02%
12	0.193	0.866	0.650		0.10%	1.02%
			8.106	0.877		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 13 von 19
 Page 13 of 19

Phase 1 100%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	dmax
1	0.182	0.818	0.548		0.10%	1.02%
2	0.177	0.796	0.504		0.10%	1.02%
3	0.186	0.836	0.585		0.10%	1.02%
4	0.190	0.854	0.623		0.10%	1.02%
5	0.185	0.832	0.575		0.10%	1.02%
6	0.187	0.841	0.594		0.10%	1.02%
7	0.192	0.863	0.643		0.10%	1.02%
8	0.189	0.850	0.614		0.10%	1.02%
9	0.181	0.814	0.539		0.10%	1.02%
10	0.187	0.841	0.594		0.10%	1.02%
11	0.186	0.836	0.585		0.10%	1.02%
12	0.188	0.845	0.604		0.10%	1.02%
			6.461	0.814		
Phase 2 100%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	dmax
1	0.174	0.782	0.479		0.10%	1.02%
2	0.181	0.814	0.539		0.10%	1.02%
3	0.181	0.814	0.539		0.10%	1.02%
4	0.188	0.845	0.604		0.10%	1.02%
5	0.190	0.854	0.623		0.10%	1.02%
6	0.191	0.859	0.633		0.10%	1.02%
7	0.179	0.805	0.521		0.10%	1.02%
8	0.185	0.832	0.575		0.10%	1.02%
9	0.183	0.823	0.557		0.10%	1.02%
10	0.176	0.791	0.495		0.10%	1.02%
11	0.181	0.814	0.539		0.10%	1.02%
12	0.182	0.818	0.548		0.10%	1.02%
			6.653	0.822		
Phase 3 100%						
Observation	PSTmeas	PSTreal	PSTcub	PLT	dc	Dmax
1	0.175	0.787	0.487		0.10%	1.02%
2	0.178	0.800	0.513		0.10%	1.02%
3	0.200	0.899	0.727		0.10%	1.02%
4	0.181	0.814	0.539		0.10%	1.02%
5	0.189	0.850	0.614		0.10%	1.02%
6	0.189	0.850	0.614		0.10%	1.02%
7	0.194	0.872	0.664		0.10%	1.02%
8	0.187	0.841	0.594		0.10%	1.02%
9	0.177	0.796	0.504		0.10%	1.02%
10	0.188	0.845	0.604		0.10%	1.02%
11	0.195	0.877	0.674		0.10%	1.02%
12	0.004	0.018	0.000		0.10%	1.02%
			6.532	0.817		

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 14 von 19
 Page 14 of 19

Power quality. DC injection.

OVERALL RESULTS: Max recorded over 3 phases

Test power level (+/- 5%)	10%	55%	100%
Recorded value	155 mA	180 mA	132 mA
as % of rated AC current	<0.13%	<0.13%	<0.13%
Limit	0.25%	0.25%	0.25%

In the table above, the worst case measure of the 3 phases is reported.

Power quality. Power Factor.

Voltage value	260V	277V	305V	Measured at three voltage levels and at full output. Voltage to be maintained within ±1.5% of the stated level during the test.
Measured value	>0.99	>0.99	>0.99	
Limit	>0.95	>0.95	>0.95	

In the table above, the worst case measure of the 3 phases is reported.

Protection. Frequency tests.

Function	Setting		Trip test		"No trip tests" ⁽¹⁾	
	Frequency	Time delay	Frequency	Time delay	Frequency /time	Confirm no trip
U/F stage 1	47.5Hz	20.1s	47.45 Hz	20.12s	47.7Hz/ 25s	No Trip
U/F stage 2	47.0Hz	0.55s	46.95 Hz	0.56s	47.2Hz/ 19.98s	No Trip
					46.8Hz/ 0.48s	No Trip
O/F stage 1	51.5Hz	90.05s	51.552 Hz	90.083s	51.3Hz/95s	No Trip
O/F stage 2	52.0Hz	0.50s	52.052 Hz	0.56s	51.8Hz/ 89.98s	No Trip
					52.2Hz/ 0.48s	No Trip

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 15 von 19
 Page 15 of 19

Protection. Voltage tests.						
Model: PVS-120-TL						
Function	Setting		Trip test		"No trip tests" ⁽¹⁾	
	Voltage	Time delay	Voltage	Time delay	Voltage/Time	Confirm no trip
U/V stage 1	240.99V	2.55s	240.04V	2.54s	244.99V/3.5s	No Trip
U/V stage 2	221.60V	0.55s	221.48V	0.54s	225.60V/2.48s	No Trip
					221.60V/0.48s	No Trip
O/V stage 1	315.780V	1.05s	315.04V	1.03s	311.78V/2.0s	No Trip
O/V stage 2	329.630V	0.55s	328.30V	0.52s	325.63V/0.98s	No Trip
					329.63V/0.48s	No Trip

Protection. Voltage tests.						
Model: PVS-100-TL						
Function	Setting		Trip test		"No trip tests" ⁽¹⁾	
	Voltage	Time delay	Voltage	Time delay	Voltage/Time	Confirm no trip
U/V stage 1	200.1V	2.55s	199.31V	2.56s	204.1V/3.5s	No Trip
U/V stage 2	184V	0.55s	183.90V	0.55s	188V/2.48s	No Trip
					221.60V/0.48s	No Trip
O/V stage 1	262.2V	1.05s	261.59V	1.02s	258.2V/2.0s	No Trip
O/V stage 2	273.7V	0.55s	272.60V	0.53s	269.7V/0.98s	No Trip
					329.63V/0.48s	No Trip

In the table above, the worst case measure of the 3 phases is reported.

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 16 von 19
 Page 16 of 19

Protection. Loss of Mains test and single phase test.

TABLE 1.1: Test results

MODELS: **PVS-120-TL**

No.	P _{EUT} ¹⁾ (% of EUT rating)	Reactive load (% of QL in 6.1.d)1)	P _{AC} ²⁾ (% of nominal)	Q _{AC} ³⁾ (% of nominal)	Run on time (ms)**	P _{EUT} (W)	V _{DC} (V)	Remarks ⁴⁾	Verdict
1	100	100	0	0	854.80	120000.0	777.0	Test A at BL	P
2	66	66	0	0	823.75	79200.0	685.0	Test B at BL	P
3	33	33	0	0	731.75	39600.0	593.0	Test C at BL	P
4	100	100	-5	-5	591.30	120000.0	777.0	Test A at IB	P
5	100	100	-5	0	627.20	120000.0	777.0	Test A at IB	P
6	100	100	-5	+5	589.20	120000.0	777.0	Test A at IB	P
7	100	100	0	-5	609.60	120000.0	777.0	Test A at IB	P
8	100	100	0	+5	599.60	120000.0	777.0	Test A at IB	P
9	100	100	+5	-5	601.90	120000.0	777.0	Test A at IB	P
10	100	100	+5	0	700.70	120000.0	777.0	Test A at IB	P
11	100	100	+5	+5	587.90	120000.0	777.0	Test A at IB	P
12	66	66	0	-5	641.75	79200.0	685.0	Test B at IB	P
13	66	66	0	-4	663.75	79200.0	685.0	Test B at IB	P
14	66	66	0	-3	670.75	79200.0	685.0	Test B at IB	P
15	66	66	0	-2	673.75	79200.0	685.0	Test B at IB	P
16	66	66	0	-1	749.75	79200.0	685.0	Test B at IB	P
17	66	66	0	1	795.75	79200.0	685.0	Test B at IB	P
18	66	66	0	2	699.75	79200.0	685.0	Test B at IB	P
19	66	66	0	3	665.75	79200.0	685.0	Test B at IB	P
20	66	66	0	4	655.75	79200.0	685.0	Test B at IB	P
21	66	66	0	5	629.75	79200.0	685.0	Test B at IB	P
22	33	33	0	-5	641.75	39600.0	593.0	Test C at IB	P
23	33	33	0	-4	659.75	39600.0	593.0	Test C at IB	P
24	33	33	0	-3	675.75	39600.0	593.0	Test C at IB	P
25	33	33	0	-2	677.75	39600.0	593.0	Test C at IB	P
26	33	33	0	-1	691.75	39600.0	593.0	Test C at IB	P
27	33	33	0	1	715.75	39600.0	593.0	Test C at IB	P
28	33	33	0	2	691.75	39600.0	593.0	Test C at IB	P
29	33	33	0	3	673.75	39600.0	593.0	Test C at IB	P
30	33	33	0	4	663.75	39600.0	593.0	Test C at IB	P
31	33	33	0	5	631.75	39600.0	593.0	Test C at IB	P
32	100	100	-10	-10	589.50	120000.0	777.0	Test A at IB	P
33	100	100	-10	-5	597.50	120000.0	777.0	Test A at IB	P
34	100	100	-10	0	611.70	120000.0	777.0	Test A at IB	P

Extract of Test report: 28111159 011
Engineering Recommendation G59 Issue 03 (September 2013)
13.1 Generating Unit Type Test Sheet
Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 17 von 19
Page 17 of 19

Protection. Loss of Mains test and single phase test.

TABLE 1.1: Test results

MODELS: **PVS-120-TL**

No.	P _{EUT} ¹⁾ (% of EUT rating)	Reactive load (% of Q _L in 6.1.d)1)	P _{AC} ²⁾ (% of nominal)	Q _{AC} ³⁾ (% of nominal)	Run on time (ms)**	P _{EUT} (W)	V _{DC} (V)	Remarks ⁴⁾	Verdict
35	100	100	-10	+5	596.10	120000.0	777.0	Test A at IB	P
36	100	100	-10	+10	585.90	120000.0	777.0	Test A at IB	P
37	100	100	-5	+10	589.00	120000.0	777.0	Test A at IB	P
38	100	100	0	+10	589.90	120000.0	777.0	Test A at IB	P
39	100	100	+5	+10	581.80	120000.0	777.0	Test A at IB	P
40	100	100	-5	-10	592.60	120000.0	777.0	Test A at IB	P
41	100	100	0	-10	600.50	120000.0	777.0	Test A at IB	P
42	100	100	+5	-10	599.90	120000.0	777.0	Test A at IB	P
43	100	100	+10	-10	592.30	120000.0	777.0	Test A at IB	P
44	100	100	+10	-5	601.70	120000.0	777.0	Test A at IB	P
45	100	100	+10	0	683.70	120000.0	777.0	Test A at IB	P
46	100	100	+10	+5	591.60	120000.0	777.0	Test A at IB	P
47	100	100	+10	+10	585.00	120000.0	777.0	Test A at IB	P

¹⁾ P_{EUT}: EUT output power

²⁾ P_{AC}: Real power flow at S1 as in Figure 1. Positive value means the power from EUT to utility. Nominal value is the 0% test condition value.

³⁾ Q_{AC}: Reactive power flow at S1 as in Figure 1. Positive value means the power from EUT to utility. Nominal value is the 0% test condition value

⁴⁾ BL: Balance condition, IB: Imbalance condition

*: Needs to be measured if any of the recorded run-on times at imbalanced condition are longer than the one recorded for the rated balance condition at test condition A

** "Run on time" must be < 2s

The filled out switch-off time values the highest among the three phase

TABLE 1.2: Test results

MODELS: **PVS-100-TL**

No.	P _{EUT} ¹⁾ (% of EUT rating)	Reactive load (% of Q _L in 6.1.d)1)	P _{AC} ²⁾ (% of nominal)	Q _{AC} ³⁾ (% of nominal)	Run on time (ms)**	P _{EUT} (W)	V _{DC} (V)	Remarks ⁴⁾	Verdict
1	100	100	0	0	756.40	100000.0	768.0	Test A at BL	P
2	66	66	0	0	871.75	66000.0	640.0	Test B at BL	P
3	33	33	0	0	885.75	33000.0	512.0	Test C at BL	P
4	100	100	-5	-5	599.50	100000.0	768.0	Test A at IB	P
5	100	100	-5	0	639.50	100000.0	768.0	Test A at IB	P
6	100	100	-5	+5	592.10	100000.0	768.0	Test A at IB	P
7	100	100	0	-5	604.80	100000.0	768.0	Test A at IB	P
8	100	100	0	+5	595.90	100000.0	768.0	Test A at IB	P

Extract of Test report: 28111159 011
Engineering Recommendation G59 Issue 03 (September 2013)
13.1 Generating Unit Type Test Sheet
Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 18 von 19
Page 18 of 19

TABLE 1.2: Test results

MODELS: **PVS-100-TL**

No.	P _{EUT} ¹⁾ (% of EUT rating)	Reactive load (% of Q _L in 6.1.d)1)	P _{AC} ²⁾ (% of nominal)	Q _{AC} ³⁾ (% of nominal)	Run on time (ms)**	P _{EUT} (W)	V _{DC} (V)	Remarks ⁴⁾	Verdict
9	100	100	+5	-5	598.50	100000.0	768.0	Test A at IB	P
10	100	100	+5	0	669.50	100000.0	768.0	Test A at IB	P
11	100	100	+5	+5	590.70	100000.0	768.0	Test A at IB	P
12	66	66	0	-5	635.75	66000.0	640.0	Test B at IB	P
13	66	66	0	-4	641.75	66000.0	640.0	Test B at IB	P
14	66	66	0	-3	653.75	66000.0	640.0	Test B at IB	P
15	66	66	0	-2	663.75	66000.0	640.0	Test B at IB	P
16	66	66	0	-1	717.75	66000.0	640.0	Test B at IB	P
17	66	66	0	1	739.75	66000.0	640.0	Test B at IB	P
18	66	66	0	2	675.75	66000.0	640.0	Test B at IB	P
19	66	66	0	3	651.75	66000.0	640.0	Test B at IB	P
20	66	66	0	4	641.75	66000.0	640.0	Test B at IB	P
21	66	66	0	5	631.75	66000.0	640.0	Test B at IB	P
22	33	33	0	-5	657.75	33000.0	512.0	Test C at IB	P
23	33	33	0	-4	659.35	33000.0	512.0	Test C at IB	P
24	33	33	0	-3	663.75	33000.0	512.0	Test C at IB	P
25	33	33	0	-2	673.75	33000.0	512.0	Test C at IB	P
26	33	33	0	-1	719.75	33000.0	512.0	Test C at IB	P
27	33	33	0	1	725.75	33000.0	512.0	Test C at IB	P
28	33	33	0	2	671.75	33000.0	512.0	Test C at IB	P
29	33	33	0	3	652.75	33000.0	512.0	Test C at IB	P
30	33	33	0	4	643.75	33000.0	512.0	Test C at IB	P
31	33	33	0	5	635.75	33000.0	512.0	Test C at IB	P

¹⁾ P_{EUT}: EUT output power

²⁾ P_{AC}: Real power flow at S1 as in Figure 1. Positive value means the power from EUT to utility. Nominal value is the 0% test condition value.

³⁾ Q_{AC}: Reactive power flow at S1 as in Figure 1. Positive value means the power from EUT to utility. Nominal value is the 0% test condition value

⁴⁾ BL: Balance condition, IB: Imbalance condition

*: Needs to be measured if any of the recorded run-on times at imbalanced condition are longer than the one recorded for the rated balance condition at test condition A

** "Run on time" must be < 2s

The filled out switch-off time values the highest among the three phase

Extract of Test report: 28111159 011
 Engineering Recommendation G59 Issue 03 (September 2013)
 13.1 Generating Unit Type Test Sheet
 Type Tested Generating Unit (>16A per phase but ≤ 17 kW 1 phase)

Seite 19 von 19
 Page 19 of 19

Protection. Frequency change, Stability test.				
	Start Frequency	Change	End Frequency	Confirm no trip
Positive Vector Shift	49.5Hz	+9 degrees		No trip
Negative Vector Shift	50.5Hz	- 9 degrees		No trip
Positive Frequency drift	49.5Hz	+0.19Hz/sec	51.5Hz	No trip
Negative Frequency drift	50.5Hz	-0.19Hz/sec	47.5Hz	No trip

Protection. Re-connection timer.					
Time delay setting	Measured delay	Checks on no-reconnection when voltage or frequency is brought to just outside stage 1 limits of table 1.			
25s	30.02s	At 320.4V	At 236.2V	At 47.4Hz	At 51.6Hz
Confirmation that the SSEG does not re-connect.		No reconnection	No reconnection	No reconnection	No reconnection

Fault level contribution.						
Time after fault	PhaseR		PhaseS		PhaseT	
[Seconds]	[Volts]	[Amps]	[Volts]	[Amps]	[Volts]	[Amps]
0.02	58.357	140.87	60.431	139.15	36.085	137.16
0.10	33.061	63.64	33.788	62.81	27.078	61.84
0.25	27.293	40.88	27.561	40.36	24.101	39.80
0.50	25.074	29.62	25.141	29.26	22.968	28.88
Time to trip	0.5s					

Self-Monitoring solid state switching. The requirement is specified in section 5.3.1. no specified test requirements.	N/A
Mechanical contactor used.	

- END OF DOCUMENT -